SecureFence Contracts

SecureFence — Contracts
1 contracts — Total value: $608,146.00
Generated: 04 Nov 2026 15:09

CONTRACT ID	DESCRIPTION	VALUE (AUD)	AWARD DATE	LOCATION	STATUS
QLD-TMR-WBB841	Supply and installation of Koala Proof Fencing RoadTek have been engaged to install Koala Proof Fencing on the Bruce Highway (Brisbane â€“ Gympie) to complete the missing fence links on the eastern and western side of the highway between Old Traveston Road & Tandur Road, Kybong. There are seven (7) attachments to this document for your reference. If you require clarification please contact Hazel Mauga (Project Manager) 0447 548 112 or email hazel.l.mauga@tmr.qld.gov.au In order to deliver this work RoadTek is going to the market to engage a supplier who can provide a full service operation which includes but is not limited to: - Supply and Installation of approximately 2065m of Koala Proof Fencing in accordance with TMR Standard Drawing 1603. - Remove approximately 154m of existing koala proof fencing as shown on the attachments and reusing of fence components (wire and steel sheets) where possible. - Markout, excavate & tidy post holes. - Supply all materials for the works including concrete, fencing components, metal flaps and so on. - Consideration of fencing with respect to drainage lines and installation of metal flaps under fence where required. - Chainwire and tie/lacing wire shall be coated with black PVC and that the galvanised steel sheet installed on the habitat side of fence shall be prepainted in the colour â€œNight Skyâ€ . - Ensure site is left in a clean and tidy manner upon completion of works. Two price options will be sought for this quote: 1. One which includes the concrete edging strip as per SD1603 2. Another forgoing the strip in favour of continuing the chain wire underneath the ground as shown in attachment no. 5 Items supplied by RoadTek : - Traffic Management - Clearing of vegetation prior to works - Earthworks to provide access to the worksite - Site Supervision (Mandatory safety prestarts with RoadTek Supervisor) - Basic site facilities (Toilet, hand washing facilities)	608,146.00	10 May 2023	Queensland	active